Row / West Row

Roads and Pavements

GROUNDWORK

INFORMATION

Notes to Contractors

It is essential that extreme care should be used in any excavations undertaken with regard to underground services. The Contractor shall ascertain for himself the position of all services by liaising with the relevant authorities prior to commencement of any excavation works.

The Contractor shall allow here or in his rates for the location, protection and working around all services encountered. (A provisional sum is included elsewhere for diversion of services where necessary)

D20: EXCAVATING AND FILLING

in each direction

Earthwork support

Excavating

Α

В

C

D

Ε

F

G

H

1

J

To reduce levels			İ
maximum depth not exceeding 0.25m	23	m3	
maximum depth not exceeding 1.00m	4186	m3	
Breaking out existing hard pavings; extra over any types of excavating irrespective of depth			
stone flag paving 50 thick	3455	m2	
brick setts paving 65 thick	45	m2	
	66	m2	i
terrazzo paving 50 thick	4070	m2	
coated macadam or asphalt 350 thick	4270	1112	
Taking up existing precast concrete kerbs; breaking up concrete foundation and haunching			
concrete kerbs with bed and haunching	817	m	
Puncturing existing hard pavings			
coated macadam or asphalt 350 thick, 3.00m centres	848	m2	

maximum depth not exceeding 1.00m; distance

between opposing faces exceeding 4.00m

High Row / West Row Darlington Heart To Collection :

m2

259

Item